

## Cottonwood Improvement District

---

### Addendum No. 3

---

DATE: January 31, 2025  
PROJECT: REHAB 2025  
OWNER: Cottonwood Improvement District  
8620 South Highland Drive  
Sandy, Utah  
ENGINEER: Greg Neff, Cottonwood Improvement District

---

Incorporate the following revisions to the Specifications, Drawings and other Contract Documents of the above-named project. General Items are not referenced. Revisions to the Specifications are referenced by section, page number, and paragraph number. Revisions to the Drawings are referenced by drawing sheet number. This addendum forms part of the Construction Documents.

**The following question is asked and answered:**

**Is there any flow data available for the 12" and 15" pipes?**

**The approximate maximum flow rate for the pipes to be lined is shown on the following page.**

## Rehab List - 2025

Up MH	Down MH	Line ID	Approx. Max Bypass Flow Rate (cfs)
<b>8" Diam</b>			
<b>16-2-54</b>	<b>16-2-53</b>	3199	0.11
<b>10" Diam</b>			
<b>17-2-24</b>	<b>17-2-25</b>	3412	0.13
<b>8" and 12" Diam</b>			
<b>9s-4-93</b>	<b>9s-4-92</b>	2311	0.25
<b>9s-4-92</b>	<b>9s-4-91</b>	2310	0.25
<b>9s-4--91</b>	<b>9s-4-90</b>	2309	0.25
<b>9s-4-90</b>	<b>9s-4-89</b>	2684	0.45
<b>9s-4-89</b>	<b>9s-4-88</b>	2334	0.45
<b>9s-4-88</b>	<b>9s-4-87</b>	2335	0.46
<b>9s-4-87</b>	<b>9s-4-120</b>	9175	0.46
<b>9s-4-120</b>	<b>9s-2-26</b>	9174	0.46
<b>9s-2-26</b>	<b>9s-2-25</b>	2100	0.46
<b>9s-2-25</b>	<b>9s-2-24</b>	2099	0.46
<b>9s-2-24</b>	<b>9s-2-19</b>	2098	0.46
<b>9s-2-19</b>	<b>9s-2-18</b>	2093	0.50
<b>9s-2-18</b>	<b>9s-2-17</b>	2092	0.50
<b>9s-2-17</b>	<b>9s-2-2</b>	2091	0.50
<b>9s-2-2</b>	<b>9s-2-3</b>	8084	0.51
<b>9s-2-3</b>	<b>9s-2-5</b>	2079	0.52
<b>9s-2-5</b>	<b>9s-2-27</b>	2103	0.54
<b>9s-2-27</b>	<b>9s-2-28</b>	2104	0.54
<b>9s-2-28</b>	<b>9s-2-29</b>	2105	0.54
<b>9s-2-29</b>	<b>9s-2-30</b>	2106	0.54
<b>9s-2-30</b>	<b>9s-2-33</b>	2110	0.59
<b>15" Diam</b>			
<b>28-1-30</b>	<b>28-1-21</b>	5875	3.30
<b>28-1-21</b>	<b>28-1-89</b>	9291	3.30